

**Premier Estimating Services**

Cell; 209-614-6485

Email; premierestimatingervices.com

**Customer;** Caleb Bell  
**Project;** Helena Vista Event Barn  
**Address;** Calistoga, Ca  
**Sqft;** 2151

PCS	FOOTAGE	SIZE	GRADE	DESCRIPTION
<b>SUBFLOOR</b>				
150	LNFT	2X6	DFPT	MUD SILL
2	18'	5 1/4"X9 1/2"	PSL	GIRDERS
6	22'	10X10	#1DF	POSTS
8	12'	10X10	#1DF	POSTS
1	8'	6X6	#1DF	POSTS
1	8'	4X6	#2DF	SQUASH BLOCKS
1	8'	4X4	#2DF	SQUASH BLOCKS
77	16'	2X12	#2DF	JOISTS/BLOCKS
6	18'	2X12	#2DF	RIM JOISTS/BLOCKS
37	23/32	4X8	T&G PLY	SUBFLOOR
1	10'	2X4	DFPT	STAIR PONY WALL
4	10'	2X4	#2DF	STAIR PONY WALL
2	12'	2X8	#2DF	STAIR LANDING
<b>DECK</b>				
2	12'	4X12	DFPT	GIRDERS
2	16'	4X12	DFPT	GIRDERS
2	16'	2X8	DFPT	LEDGER
5	14'	2X8	DFPT	JOISTS
18	12'	2X8	DFPT	JOISTS
1	16'	4X4	DFPT	POSTS
4	12'	2X12	DFPT	STAIR STRINGERS
1	16'	2X4	DFPT	KNEE BRACES
360	SQFT	UNSPECIFIED DECKING		
<b>1ST FLR FRAME</b>				
80	LNFT	2X6	DFPT	BOTTOM PLATE
1000	LNFT	2X6	#2DF	PLATE STOCK
180	10'	2X6	#2DF	STUDS
40	16'	2X6	#2DF	RAKE STUDS
8	10'	4X6	#2DF	HD POSTS
4	16'	4X6	#2DF	HD POSTS
5	10'	6X6	#1DF	HD POSTS
32	LNFT	6X6	#1DF	EXTERIOR HEADERS
32	LNFT	6X8	#1DF	EXTERIOR HEADERS
2	10'	6X10	#1DF	EXTERIOR HEADER
48	15/32"	4X10	OSB PLY	SHEAR
8	15/32"	4X8	OSB PLY	SHEAR
<b>LOFT FRAME</b>				
1	30'	10X16	#1DF	TRUSS BEAM
1	30'	10X10	#1DF	TRUSS BEAM

**Premier Estimating Services**

Cell; 209-614-6485

Email; premierestimatingervices.com

PCS	FOOTAGE	SIZE	GRADE	DESCRIPTION
3	30'	10X12	#1DF	BEAMS
8	10'	10X12	#1DF	BEAMS
4	10'	4X6	#1DF	TRUSS WEB
15	18'	4X12	#1DF	LOFT JOISTS/STAIR STRINGERS
1	8'	4X12	#1DF	LOFT JOISTS
2	16'	3X12	#1DF	LOFT JOISTS BLOCKING
50	16'	2X6	T&G DF	LOFT DECKING
16	20'	2X6	T&G DF	LOFT DECKING
16	23/32	4X8	T&G PLY	SUBFLOOR
4	16'	3X12	#1DF	STAIR TREADS
4	10'	4X6	#1DF	KNEE BRACE @ WALL 11/S6.1
18	8'	8X8	#1DF	KNEE BRACE @ WALL 15/S6.1
<b>2ND FLR FRAME</b>				
20	LNFT	3X6	#2DF	3X SILL
700	LNFT	2X6	#2DF	PLATE STOCK
80	10'	2X6	#2DF	STUDS
30	16'	2X6	#2DF	RAKE STUDS
40	18'	2X6	#2DF	RAKE STUDS
3	10'	4X6	#2DF	HD POSTS
6	16'	4X6	#2DF	HD POSTS
3	10'	6X6	#1DF	HD POSTS
2	16'	6X6	#1DF	HD POSTS
2	18'	6X6	#1DF	HD POSTS
1	12'	6X12	#1DF	EXTERIOR HEADER
1	10'	6X10	#1DF	EXTERIOR HEADER
110	LNFT	6X6	#1DF	EXTERIOR HEADERS
33	15/32"	4X10	OSB PLY	SHEAR
12	15/32"	4X8	OSB PLY	SHEAR
<b>LOW ROOF</b>				
15	22'	3X12	#1DF	RAFTERS
4	18'	2X12	#2DF	LEDGER
2	18'	2X10	#2DF	EAVE BLOCKS
100	20'	2X6	T&G DF	ROOF DECKING
25	15/32"	4X8	OSB PLY	RADIANT BARRIER
34	12'	2X4	#2DF	ROOF SLEEPERS
14	10'	2X4	#2DF	OUTRIGGERS
48	LNFT	2X10	REDWOOD	FASCIA - VERIFY
60	LNFT	2X8	REDWOOD	BARGE RAFTERS - VERIFY
<b>HIGH ROOF</b>				
30	20'	3X12	#1DF	RAFTERS
4	18'	3X12	#1DF	BLOCKING
13	24'	3X10	#1DF	COLLAR TIES
2	14'	6X12	CEDAR	HOIST BEAMS
2	18'	3X16	#1DF	RIDGE BLOCKS

**Premier Estimating Services**

Cell; 209-614-6485

Email; premierestimatingervices.com

PCS	FOOTAGE	SIZE	GRADE	DESCRIPTION
2	18'	2X10	#2DF	EAVE BLOCKING
2	18'	2X4	#2DF	EAVE BLOCKING
40	12'	2X4	#2DF	ROOF SLEEPERS
16	10'	2X4	#2DF	OUTRIGGERS
200	20'	2X6	T&G DF	ROOF DECKING
50	15/32"	4X8	OSB PLY	RADIANT BARRIER
90	LNFT	2X10	REDWOOD	FASCIA - VERIFY
48	LNFT	2X8	REDWOOD	BARGE RAFTERS - VERIFY
<b>HARDWARE</b>				
12	HDU2-SDS2.5			
80	5/8"X3"X3" SLOTTED GALV PLATE WASHERS			
80	5/8" ROUND WASHERS			
9	5/8"X16" GALV ALL THREAD			
9	5/8" GALV COUPLERS			
2	PC6Z			
3	PC4Z			
2	EPC4Z			
4	EPC6Z			
2	GH410-8			
2	MBHU5.50/9.25KT			
150	SDS25412			
150	SDS25600			
250	SDWS22800			
400	A35			
52	HU28			
2	CJT4Z			
38	CJT5Z			
20	CJT6Z			
2	HCJTZ			
52	TA10Z			
400	SDS 1/4"X1 1/2"			
27	DTT2Z			
20	1/2"X12" GALV ALL THREAD			
5	1/2"x10" GALV MACHINE BOLTS			
9	1/2"x 8" GALV MACHINE BOLTS			
2	1/2"x 6" GALV MACHINE BOLTS			
54	1/2" GALV NUTS			
68	1/2" GALV WASHERS			
32	5/8"X12" MACHINE BOLTS			
64	5/8" NUTS			
64	5/8" WASHERS			
1	CS16			
15	MSTA15			
17	CBTZ4			



***Premier Estimating Services***

Cell; 209-614-6485

Email; premierestimatingervices.com

<b>PCS</b>	<b>FOOTAGE</b>	<b>SIZE</b>	<b>GRADE</b>	<b>DESCRIPTION</b>
22	LSTA12			
4	MSTC28			
15	MSTA24			
6	VB5			
20	TUBES OF SUBFLOOR ADHESIVE			